


To CC

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 4 Twp. 24 Rge. 14 (E) W (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE SE SE
Lease Owner John Lindas Oil, Inc.
Lease Name Suiter Well No. 1
Office Address P. O. Box 470, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-11-1950
Application for plugging filed 1-11-1950
Application for plugging approved 1-11-1950
Plugging commenced 1-11-1950
Plugging completed 1-12-1950
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 4300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 215'. Set wood plug and 15 sacks of cement.
Filled hole with mud to 35'. Set wood plug and 10 sacks cement.

1-18-51
STATE CORPORATION COMMISSION
JAN 18 1951
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to John Lindas Oil, Inc.
Address P. O. Box 470, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Scott Stuckey (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) By: Scott Stuckey JOHN LINDAS OIL, INC.
1316 Union Nat'l Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of January, 1951.
Mabel Pally Notary Public.

My commission expires February 11, 1951 22-7377-B 4-49-10M

PLUGGING
FILE SEC 4 TWP 24 R 14 W
BOOK PAGE 55 LINE 78

DRILLING LOG

To CC

To: National Cooperative Refinery Association
Union National Bank Building
Wichita 2, Kansas

Lease: Suiter #1 County: Stafford, Kansas
Section: 4-24-11W
Location: SE SE SE

Rotary Total Depth: 4300'
Commenced: 12-27-50, Completed: 1-12-51.
Casing: 8-5/8" @ 215'
5-1/2" @ None.

Contractor: John Lindas Oil, Inc.
1316 Union National Bank Building
Wichita 2, Kansas

Figures Indicate Bottom of Formations

0	to	40	Soil and Clay
40		100	Sand and Gravel
100		215	Shale and Shells
215		365	Blue Shale
365		415	Sand
415		675	Shale and Red Bed
675		890	Shale, Red Bed, and Sand
890		915	Anhydrite
915		1360	Shale and Shells
1360		1780	Shale, Shells and Salt
1780		1870	Shale, and Lime, Shells
1870		1960	Lime and Shale
1960		2335	Lime
2335		2500	Lime and Shale
2500		2645	Shale and Shells
2645		3205	Shale and Lime
3205		3295	Lime and Shale
3295		3535	Lime
3535		3605	Lime Broken
3605		3985	Lime
3985		3999	Conglomerate
3999		4023	Viola Lime
4023		4030	Lime
4030		4090	Lime and Shale
4090		4105	Chert and Lime
4105		4128	Cherty Lime and Shale
4128		4155	Shale and Chert
4155		4205	Chert and Shale
4205		4225	Cherty Shale and Sand
4225		4235	Arbuckle
4235		4300 TD	Lime Arbuckle.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1951
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

JOHN LINDAS OIL, INC.

PLUGGING
FILE SEC 4 T 24 R 14W
BOOK PAGE 55 LINE 78

By Scott Stuckey

Subscribed and sworn to before me, this 16th day of January, 1951.

Mabel Dally
NOTARY PUBLIC

My Commission expires the 11th day of February, 1954.