

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit

Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 61S Twp. 24S Rge. 14W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/4
Lease Owner Musgrove Petroleum Corp.,
Lease Name Crouse Well No. 1
Office Address KFH Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.
Date well completed September, 17, 1950. 19
Application for plugging filed September, 17, 1950. 19
Application for plugging approved September, 17, 1950. 19
Plugging commenced September, 17, 1950. 19
Plugging completed September, 17, 1950. 19
Reason for abandonment of well or producing formation Dry Hole.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C.D. Slough, Great Bend, Kansas.
Producing formation 4150 Depth to top 4150 Bottom 4150 Total Depth of Well 4150 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	213'	8-5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 213' feet to 30' feet for each plug set.

Used Halliburton plugs. Pushed to depth 213' cemented with 15-sacks cement through drill pipe. Cemented one plug to 30' with 10-sacks cement.

9-23-50

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1950
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Musgrove Petroleum Corp., KFH Building,
Address Wichita, Kansas.

STATE OF Kansas, COUNTY OF Rice, ss.
Stag Drilling Inc., (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. L. Darnell Pres.
Chase, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 22 day of September, 1950

Claudio Miller
Notary Public.

My commission expires 2/1/51

PLUGGING
FILED SEP 24 1950
FILED 29 1950 U

COPY

COPY

CONTRACTOR'S WELL LOG

Operator Musgrove Petroleum Corp. Farm Name Crouse #1
 Location NW/4 NW/4 SE/4 of Sec. 6 Twp. 24S Rge. 14W
 Pool Name _____ County Stafford State Kansas
 Commencement Date 8/31/50 Completion Date 9/17/50

LOG OF WELL

All measurements from top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	150	Clay-sand		
150	200	Shale		
200	213	Shale-shells		
213	565	Shale-shells	1/2° - 500'	
565	915	Red Bed		
915	935	Anhydrite		
935	1385	Shale-shells	1/2° - 1021'	
1385	1525	Salt	1/4° - 1504'	
1525	1760	Shale-shells		
1760	1845	Broken lime		
1845	2020	Lime		
2020	2070	Broken lime		
2070	2110	Lime-shale		
2110	2220	Broken lime		
2220	2306	Lime		
2306	2530	Shale-lime-shells	1° - 2507'	
2530	2645	Lime-shale		
2645	2740	Shale-lime-shells		
2740	2970	Shale-shells		
2970	3300	Lime-shale	1/4° - 3022'	
3300	3865	Lime		
3865	3990	Lime shale		
3990	4047	Chertz-lime		
4047	4068	Shale		
4068	4075	? Not up		
4075	4107	Shale		
4107	4120	Lime ?		
4120	4150	Arbuckle		
		Total Depth		DRY HOLE

Set 213' (12 jts.) 8-5/8" surface pipe

State of Kansas)
) SS
 County of Rice)

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.


STAG DRILLING INC.

By /s/ C. L. Tyrrell

Subscribed and sworn to before me this 22nd day of September, 1950.

My commission expires: 3-1-51

(SEAL)



RECEIVED
 /s/ Orlando Malter
 Notary Public
 OCT 14 1950
 CONSERVATION DIVISION
 Wichita, Kansas