


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH

Locate well correctly on above  
Section Plat

Stafford

County. Sec. 5 Twp. 24 Rge. (E) 14 (W)Location as "NE/CNW/SW" or footage from lines SW/SW/NWLease Owner Lewis Drilling CompanyLease Name LaudickWell No. 1Office Address 915 Union Center - Wichita 2, KansasCharacter of Well (completed as Oil, Gas or Dry Hole) Dry HoleDate well completed 4-22 1957Application for plugging filed 4-22 1957Application for plugging approved 4-22 1957Plugging commenced 4-22 1957Plugging completed 4-22 1957

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19Was permission obtained from the Conservation Division or its agents before plugging was commenced? YesName of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set to bottom plug at 240' with 20 sacks cement. Filled with mud to 40', set top plug with 10 sacks cement- Filled to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company  
Address 915 Union Center - Wichita 2, KansasSTATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. Fred Hambright(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.(Signature) J. Fred Hambright915 Union Center - Wichita 2, Kansas  
(Address)SUBSCRIBED AND SWORN TO before me this 29 day of April, 19 57A.R. Derrington

Notary Public.

My commission expires 8-20-60

RECEIVED  
5-9-1957  
CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING  
FILE SEC 5 T 24 R 14 W  
BOOK PAGE 8 LINE 11

WELL LOG

COMPANY Lewis Drilling Company

SEC. 5 T. 24S R. 14W  
LOC. SW/SW/NW

FARM Laudick

NO. 1

TOTAL DEPTH 4145'

COMM. 4-12-57


COMP. 4-22-57

COUNTY Stafford  
KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20 10  
15 8 5/8" - 200'  
12 6  
13 5

ELEVATION 1989 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-75	Sandy Clay
75-140	Red beds
140-200	Shale
200-1850	Red beds and shale
1850-2055	Shale & Lime
2055-2185	Lime
2185-3638	Lime and shale
3638-3980	Lime
3980-4060	Lime & Chert
4060-4145	Lime & Shale
4145	T.D.

Geologic Tops

Heebner Shale	3475
Brown Lime	3617
Lansing	3627
B/Kansas City	3850
Viola	3970
Simpson Shale	4042
Arbuckle	4099

PLUGGING

FILE SEC 5 T. 24 R. 14W  
BOOK PAGE 8 LINE 11

State of Kansas

County of Sedgwick

SS:

I, J. Fred Hambright

of the

Lewis Drilling

Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Laudick #1 well.

Subscribed and sworn to before me this

29

day of April

1957

My Commission Expires: 8-20-60

A. R. Derrington NOTARY PUBLIC