

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 185-22,944-0000

LEASE NAME Learned

WELL NUMBER 1

600 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 25 TWP. 24S RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 5-12-00

Plugging Completed 5-16-00

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Honey Oil Company, Inc.

ADDRESS 8526 Boxhorn Wichita, Kansas 67226

PHONE/(316) 265-7300 OPERATORS LICENSE NO. 30080

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3894'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	253'	None
				5-1/2"	3892'	2610'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each. Plugged off bottom with sand to 3590' and 5 sks. cement. Shot pipe @2610', pulled casing, plugged surface with 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel, 100# hulls, 8-5/8" wiper plug and 125 sks. cement, 60/40 pos. 6% gel.

Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Honey Oil Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 22 2000

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the above-described well as stated in the statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of May, 2000

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



Form CP  
Revised 05-