

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-047-21425-0000
LEASE NAME Hammeke Trust
WELL NUMBER 1-14

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1045 Ft. from South Line of Section
2970 Ft. from East Line of Section

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION 275' S of E/2 E/2 SW
ADDRESS P.O. Box 780167 Section 14 Township 24s Range 16W
CITY, STATE, ZIP Wichita, Kansas 67278-0167 County Edwards
PHONE # 316-684-8481 Date Well Completed July 15, 1997
Character of Well Dry and Abandoned Date Plugging Commenced July 15, 1997
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed July 15, 1997

The plugging proposal was approved on July 11, 1997 at 9:00 am (date)
by Mike Maier (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes

Producing Formation(s) D&A Depth to Top Bottom T.D. 4360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	120	and		
Redbeds	Shale	120	275	8-5/8"	258.86	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Heavy mud from RTD to 1100', then 50 sacks,
Heavy mud to 550', then 40 sacks. Heavy mud to 300', then 50 sacks,
Heavy mud to 40' then 10 sacks,
Plugged rathole with 15 sacks and mousehole with 10 sacks.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 18th day of July, 19 97



[Signature]
(Notary Public)

7-21-97
RECEIVED
KANSAS CORP COM
1997 JUL 21 P 11:22

My Commission Expires: _____

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Hammeke Trust 1-14

LOCATION: 275' S of E/2 E/2 SW
API: 15-047-21425

Section 14 T 24s R 16W
Edwards County, Kansas

OWNER: F.G. Holl Company, L.L.C.

COMMENCED: 08-Jul-97

CONTRACTOR: Sterling Drilling Company, Rig #4

COMPLETED: 15-Jul-97

TOTAL DEPTH:	DRILLER	4360	FEET
	LOGGER	4361	FEET

Ground Elevation: 2058

KB Elevation: 2067

LOG

0 -	120 FEET	Top Soil and Sand
120 -	1043 FEET	Shale
1043 -	1063 FEET	Anhydrite
1063 -	4360 FEET	Limestone, Shale and Dolomite

CASING RECORDS

Spud @ 9:45 am on 7-8-97. Drilled 12-1/4" hole to 275'. Ran 6 joints of new 23# 8-5/8" surface casing 258.86' set at 270' KB. Cemented with 210 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 3:15 pm on 7-8-97 by HOWCO. Good returns. Ticket # 219244.

Received plugging orders at 9:00 am on 7-11-97 from Mike Maier

Plugged well with: Heavy mud from RTD to 1100', then 50 sacks,
Heavy mud to 550', then 40 sacks. Heavy mud to 300', then 50 sacks,
Heavy mud to 40' then 10 sacks,
Plugged rathole with 15 sacks and mousehole with 10 sacks.

Started plugging at 12:00 noon. Plug down at 1:45 pm on 7-15-97 by HOWCO using 60/40 Poz, 6% Gel, 1/4# Floseal. Ticket # 219342.

DEVIATION SURVEYS

1/2	degree(s) at	275	feet
1	degree(s) at	3867	feet
1	degree(s) at	4256	feet

RECEIVED
KANSAS CORP COM
1997 JUL 21 P 1:22