

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County. Sec. 16 Twp. 24S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines. CNW SE

Lease Owner Branine-Holl

Lease Name Rudd Well No. 1

Office Address 6427 E. Kellogg - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19 \_\_\_\_\_

Application for plugging filed \_\_\_\_\_ 19 \_\_\_\_\_

Application for plugging approved \_\_\_\_\_ 19 \_\_\_\_\_

Plugging commenced \_\_\_\_\_ January 28 19 57

Plugging completed \_\_\_\_\_ February 1 19 57

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4353' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286'	None
				5-1/2"	4352'	3407'
				Packer set at 4275 1/2' and casing perforated from 4258' to 4268'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 4375 1/2' to 4245' and ran 5 sacks of cement. Pulled casing up to 1700' and circulated the hole with 40 sacks of jell mud. Set a rock bridge from 275' to 265' and ran 20 sacks of cement which filled to 212'. Mudded the hole to 35', set a 10' rock bridge and ran 10 sacks of cement to base of cellar. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Robert L. Hoover (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. Hoover

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 9th day of April, 19 57

My commission expires August 5, 1957

Mary E. Lacey Notary Public.

Note: Plugging fee payment receipt received from Alexander Indlg. Co, Tulsa, Okla.

PLUGGING  
FILE SEC 16 T. 24 R. 16W  
BOOK PAGE 137 LINE 6  
DIVISION.  
Wichita, Kansas

4-10-57

WELL LOG ON RUDD #1

Spudding date: 6/20/56  
 Date casing set: 6/20/56  
 Date rotary completed: 7/3/56  
 Date cable completed:

Location:

Section 16-24S-16W, Edwards County, Kansas

FROM	TO	FORMATION	REMARKS
0	286	Surface Hole	Ran 14 Jts. 8-5/8" 24# Casing - set at 286' and cemented w/200 Sx. Pozmix w/200# C.C.
286	1500	Shale & Shells	
1500	1860	Shale	
1860	2010	Shale & Shells	
2010	2230	Shale	
2230	2800	Shale & Lime	
2800	3245	Shale	
3245	3365	Shale & Shells	
3365	3640	Shale & Lime	
3640	3738	Shale	
3738	3830	Shale & Lime	Ran 135 Jts. 5 1/2" Casing - set at 4352' and cemented w/75 Sx. Pozmix.
3830	4151	Lime	
4151	4261	Lime & Shale	
4261	4288	Lime	
4288	4293	Chat & Chert	
4293	4359	Shale & Lime	
4359		Total Depth	

Subscribed and sworn to before me this 10th day of July, 19 56

I certify the above and foregoing to be a true and exact copy of the original driller's log on the Rudd #1

HERNDON DRILLING COMPANY

Lundy Cooper  
 Notary Public  
 My commission expires: 1/27/60

By: [Signature]  
 Title: Assistant Secretary

PLUGGING  
 FILE SEC 16 T 24 R 16W  
 BOOK PAGE 137 LINE 6

APR 10 1956  
 CONSERVATION DIVISION  
 WICHITA, KANSAS