

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,677-0000

LEASE NAME Rudd A

WELL NUMBER 3-16

1680 Ft. from S Section Line

4950 Ft. from E Section Line

30"N SW NW SW
SEC. 16 TWP. 24S RGE. 16 ~~KEXXX(W)~~

COUNTY Edwards

Date Well Completed _____

Plugging Commenced March 3, 1994

Plugging Completed March 4, 1994

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl Co

ADDRESS P O Box 780167 Wichita, Ks. 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Dodge City office (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4485

PBTD: 4340

Show depth and thickness of all water, oil and gas formations. Perfs: 4367-71 & 4289-93.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	279	8 5/8	279	0
		0	4472	4 1/2	4472	65 jts. 2382 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
3-3-94: Dumped 2 1/2 bbls. of sand, sand at 4130. Dumped 4 sx. cement on top of sand.
3-4-94: Cut off casing at 2382 ft, recovered 65 jts of 4 1/2" casing. Rigged down and moved out.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P O Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl Co

STATE OF Kansas COUNTY OF Pratt, ss.


Judy Berry

(Employee of Pratt Well Service, Inc.) of Pratt, Kansas

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) c/o Pratt Well Service, Inc.



Subscribed AND SWORN TO before me this 8th day of March, 1994

Dorothy M. Furgason
Notary Public

My Commission Expires: February 6, 1997

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - RUDD ESTATE #3-16
Located: 960' FNL; 330' FNL, SW/4, Section 16-24S-16W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 25, 1980
COMPLETED: October 31, 1980

TOTAL DEPTH: 4485'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Sand	Ran 6 joints used 8 5/8", 28# casing. 266.99' set at 279' K.B. Cemented with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 7:00 PM, 10-25-80, by Howco.
90 - 282 Clay, Shale	
282 - 940 Shale, Sand and Red Beds	
940 - 1095 Shale	
1095 - 1108 Anhydrite	
1108 - 1761 Shale	
1761 - 4395 Lime and Shale	
4395 - 4485 Chat, Lime, Shale	Ran 12 joints used 4 1/2", 10.5# OD casing and 112 joints new 4 1/2", 10.5# OD casing, 4473.23' set at 4461' K.B. Cemented with 225 sacks Regular Mix. Plug down at 4:40 PM, 10-31-80, by Howco.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 08 1994

CONSERVATION DIVISION
WICHITA, KS

Deviation Surveys: 1 1/4° at 2131'
2° at 4340'