

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,624-0000

LEASE NAME Dutton

WELL NUMBER 2-17

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 17 TWP. 24 RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 7-27-90

Plugging Completed 8-9-90

LEASE OPERATOR F.G.Holl Company

ADDRESS Box 158 Belpre, KS. 67519

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	256'	none
				4 1/2"	4398'	2448'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mixed 100# hulls and 30 sacks cement w/1200 PSI @400'. Shot pipe @2640', 2438'. Mixed 100 hulls in w/30 cement chase w/ rubber plug to 400' where it squeezed off w/200 PSI.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. AUG 15 1990

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 14 day of August, 19 90

Irene Herzberg
Notary Public

My Commission Expires: 

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- DUTTON #2
Located: C/SE/4, Section 17-24S-16W, Edwards County, Kansas

OWNER: F. G. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 11, 1980
COMPLETED: February 17, 1980

TOTAL DEPTH: 4400'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 122 Sand	Ran 6 joints used 28#, 8 5/8" casing. 244.02' set at 256' K.B. Cemented with 225 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 12:15 AM, 2-12-80, by Howco.
122 - 259 Shale and Sand Strs.	
259 - 1099 Shale, Sand and Red Bed	
1099 - 1118 Anhydrite	
1118 - 1330 Shale	
1330 - 2585 Lime and Shale	
2585 - 2870 Lime and Shale Strks.	Ran 105 joints 10.5#, 8RD, 4 1/2" casing. 4387.79' set at 4398' K.B. Cemented with 175 sacks 50/50 Pozmix with 2% gel, 18% salt, 5# gilsonite per sack and 3/4 of 1% CFR-2 per sack. 100' rotating scratchers. Plug down at 9:45 PM, 2-17-80, by Howco.
2870 - 4400 Lime and Shale	

RECEIVED
STATE COMMISSION

Deviation Surveys: 1° at 2185'
1 1/2° at 4281'

MAY 29 1980
CONSERVATION DIVISION
Wichita, Kansas