

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER. 15-047-21,126-0000

LEASE NAME Dutton

WELL NUMBER 1-17

 Ft. from S Section Line

 Ft. from E Section Line
NE NW NE

SEC. 17 TWP. 24 RGE. 16W(E)or(W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 3-4-88

Plugging Completed 4-6-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl Company

ADDRESS 6427 E. Kellogg
Wichita, Kansas 67207

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4420'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	264'	none
				4-1/2"	4410'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4260' and 4 sacks cement. Shot pipe @2405', 2200', pulled a total of 54 joints of 4-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull and 130 cement.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 7th day of April, 19 88

[Signature]
Notary Public

My Commission Expires:



APR - 8 1988

Form CP-4
Revised 07-86

CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- DUTTON #1-17

Located: NE NW NE, Section 17-24S-16W, Edwards County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 24, 1983

COMPLETED: October 30, 1983

TOTAL DEPTH: 4420'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 24# casing.
90 - 267 Shale	252.44' pipe set at 264' K.B. Cemented with 210 sacks 60/40 Pozmix plus 3% cc. Plug down at 6:30 PM, 10-24-83, by Howco.
267 - 740 Shale, Sand and Red Bed	
740 - 1470 Shale	
1470 - 4420 Lime and Shale	Ran 105 joints 4 1/2", 10.5# casing (11 joints were used). 4401.08' pipe set at 4410' K.B. Cemented with 100 sacks Lite and 125 sacks 50/50 Pozmix, plus our regular additives. Plug down at 2:00 PM, 10-30-83, by Howco. Plugged rathole. Did not plug water well.

STATE OF KANSAS
COMMISSION

FEB 18 1988

CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 3/4° at 2140'
1° at 4288'