

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Edwards County, Sec. 21 Twp. 24 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner F. G. Holl

Lease Name Lunz Well No. 1

Office Address 6427 E. Kellogg, Wichita, Kansas 67207

Character of Well (completed as Oil, Gas or Dry Hole) OWWO

Date well completed Nov. 11 19 67

Application for plugging filed April 23 19 74

Application for plugging approved 19

Plugging commenced June 27 19 74

Plugging completed July 10 19 74

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4675 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	336'	8 5/8"	336'	none
			4375'	5 1/2"	4375'	2394.10

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 4100' with 25' of sand and 5 sacks of cement.

Allied Cementing Company plugged well pumping in 2 sacks of hulls, 10 sacks of gel and 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, SS.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 74

My commission expires Feb. 10, 1975

Seay A Meyer Notary Public

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY D.R. LAUCK OIL CO., INC.

SEC. 21 T. 24 R. 16W

FARM Lunz "A" NO. 1

LOG: NW NW SW

TOTAL DEPTH 4675'

COUNTY Edwards

COMM. 10-30-67


COMP. 11-11-67

SHOT OR TREATED

CONTRACTOR D.R. Lauck Oil Co., Inc.

ISSUED 12-16-67

KANSAS



CASING

20 10
15 8 5/8 2326' w/225 sx cem.
12 6
13 5 1/2 2304'

ELEVATION 2082' KB

PRODUCTION DRY/ARB.

FIGURES INDICATE BOTTOM OF FORMATIONS

FL0 100 MCF GPD

Sand	170
Shale	327
Red Bed	585
Sand	615
Red Bed, some sandy	1095
Anhydrite	1115
Shale	1434
Shale & shells	1875
Shale & lime	2150
Lime & shale	2590
Shale & lime	2710
Lime & shale	3785
Shale	3822
Lime	4130
Lime & shale	4253
Miss.	4288
Shale	4314
Shale & lime	4365
Shale	4369
Viola	4557
Cher, Lime & shale	4577
Sand	4583
Shale	4638
Arbuckle	4650
Lime	4675 RTD

Anhydrite (driller)	1095 +987
Heebner	3638-1606
Toronto	3714-1632
Douglas	3729-1647
Brown Lima	3822-1740
Lansing	3834-1752
Mississippian	4255-2173
Kinderhook	4290-2208
Viola	4369-2287
Simpson	4560-2473
Arbuckle	4636-2554
Total Depth	4675-2593

DST #1 (H) 4256-70, open 1 hour, good blow. Recovered 40' mud.
ISIP 507#, 30 min.
FSIP 733#, 30 min.
IFP 18#
FFP 35#

D&A

*OWWO
5-6-71
J. G. Hall, cont: string
Lunz #1
Ran log to 4396'
5 1/2" 4396' 100 cf Cem.*

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 - 1974

CONSERVATION DIVISION
Wichita, Kansas

*FL0 100 MCF GPD
Miss. 4260-72
& Kind. 4321-24*