

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,884-0000

LEASE NAME Skalsky 3-22

WELL NUMBER

SPOT LOCATION 594' FNL, 330' FEL SE/4

SEC. 22 TWP. 24 SRGE. 16 (W) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 8/22/85

Plugging Completed 10/28/85

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg, Wichita, Ks. 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 4385'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	252'	none
				4 1/2"	4380'	2804'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bototm with sand to 3775' & 4 sacks cement. Shot pipe at 3516', 3212', 3012', 2917', & 2804'. Pulled 71 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8 5/8 plug, & 150 sacks 60/40 poz 6% gel.

Plugging compelte.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of October, 19 85

RECEIVED
STATE CORPORATION COMMISSION
Notary Public

My Commission expires:



OCT 31 1985

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - SKALSKY #3

Located: 594' FNL; 330' FEL, SE/4, Section 22-24S-16W,
Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 30, 1981

COMPLETED: July 7, 1981

TOTAL DEPTH: 4385'

LOG

0 - 101 Surface Soil and Sand
101 - 255 Clay, Shale and Sand Str.
255 - 288 Shale and Sand
288 - 1055 Shale, Sand and Red Beds
1055 - 1072 Anhydrite
1072 - 1155 Shale
1155 - 2050 Shale and Lime Strs.
2050 - 4385 Lime and Shale

CASING RECORD

Ran 6 joints new 8 5/8", 24# casing.
239.83' pipe set at 252' K.B. Cemented
with 210 sacks 60/40 Pozmix with 3% cc.
Plug down at 2:30 PM, 6-30-81, by Howco.

Ran 111 joints 4 1/2" 10.5# new
casing. 6 joints have been sand blasted.
4370.90' pipe set at 4380' K.B.
Cemented with 225 sacks regular mix.
Plug is at 4377'. Plug down at 3:30 AM,
7-7-81, by Howco.

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1985

CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 1° at 2203'
1° at 3357'