

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-20,719-0000

LEASE NAME Skalsky

WELL NUMBER 2-22

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 22 TWP. 24 SRGE. 16 W. (E) or (W)

COUNTY Edwards

Date Well Completed         

Plugging Commenced 3/6/89

Plugging Completed 3/21/89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F.G. Holl  
c/o Art Merrick

ADDRESS P.O. Box 158  
Belpre, KS 67519

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, Is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
				8 5/8	274	none
				4 1/2	4359	2333

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
Plugged bottom with sand to 3770', ran 4 sacks cement, shot @2503',  
2390', 2333', plugged surface with 400# hulls, 10 gel, 50 sacks cement,  
10 gel, 100# hulls, 8 5/8" plug, 125 sacks 60/40 poz 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 89

Jane L. Hoover  
Notary Public

My Commission Expires:         



STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- SKALSKY #2  
Located: 75' FNL; 11.70' FEL; SE/4, Sec. 22-24S-16W,  
Edwards County, Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 5, 1980  
COMPLETED: August 11, 1980

TOTAL DEPTH: 4360'

LOG

CASING RECORD

0 - 190 Sand  
190 - 277 Clay, Shale  
277 - 415 Shale, Sand and Red Bed  
415 - 1190 Red Beds and Shale  
1190 - 2050 Shale and Shells  
2050 - 3678 Lime and Shale  
3678 - 3995 Lime  
3995 - 4340 Lime and Shale  
4340 - 4360 Lime

Ran 6 joints 28#, 8 5/8" used casing,  
262.12' set at 274' K.B. Cemented with  
225 sacks 60/40 Pozmix with 3% cc. Plug  
down at 9:30 PM, 8-5-80, by Howco.

Ran 10 joints 10.5#, 4 1/2" OD used  
casing and 110 joints 10.5#, 4 1/2"  
OD new casing. 4349.06' set at 4359'  
K.B. Cemented with 75 sacks Light and 150  
sacks 50/50 Pozmix with 18% salt, 3/4 of  
1% CFR-2; 5# gilsonite per sack, 1/4#  
nylon fiber per sack and 1/8# floseal  
per sack. 250 gal. mud flush and 20  
bbls. salt flush ahead. Plug down at  
8:00 PM, 8-11-80, by Howco.

Deviation Surveys: 1° at 2210'  
1 3/4° at 3855'