

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,196-0000

LEASE NAME Skalsky

WELL NUMBER #4-22

           Ft. from S Section Line

           Ft. from E Section Line

SEC. 22 TWP. 24S RGE. 16W or (W)

COUNTY Edwards

Date Well Completed           

Plugging Commenced 3/1/89

Plugging Completed 3/21/89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F.G. HOLL

ADDRESS c/o Art Merrick  
P.O. Box 158

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on            (date)

by            (KCC District Agent's Name).

Is ACO-1 filed?            If not, Is well log attached?           

Producing Formation            Depth to Top            Bottom            T.D. 4395'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	272	none
				4 1/2	4394	2244

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1989  
CONSERVATION DIVISION  
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Plugged bottom with sand to 4200', ran 4 sacks cement, shot @2824',  
2590', 2506', 2423', 2244', plugged surface with 400# hulls, 10 gel,  
50 sacks cement 10 gel, 100# hulls, 8 5/8" plug, 125 sacks 60/40 poz  
6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 89

James Hoover  
Notary Public

My Commission Expires:           



## STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - SKALSKY #4-22  
 Located: SE NE NE, Section 22-24S-16W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 2, 1984

COMPLETED: August 9, 1984

TOTAL DEPTH: 4395'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 23# casing. 259.57' pipe set at 272' K.B.
90 - 275 Shale	Cemented with 210 sacks 60/40 Pozmix, with 3% cc. Plug down at 11:45 AM,
275 - 775 Shale and Sand	8-2-84, by Howco.
775 - 1050 Shale and Red Beds	
1050 - 1070 Anhydrite	
1070 - 1785 Shales	
1785 - 4395 Lime and Shale	Ran 109 joints 4 1/2", 10.5# casing. 16 joints were used. 4384' pipe set at 4394' K.B. Cemented with 100 sacks Lite, 125 sacks 50/50 Pozmix plus our regular additives. Plugged rathole and water well. Plug down at 1:15 AM, 8-9-84, by Howco.

Deviation Surveys: 0° at 2105'  
 1/2° at 3844'  
 1/4° at 4270'