

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,184-0000

LEASE NAME Hacker

WELL NUMBER 2-31

SPOT LOCATION NE NE NW

SEC. 31 TWP. 24 RGE. 16 (W)

COUNTY Edwards

Date Well Completed 6-27-84

9:00 AM

Plugging Commenced 6-27-84

10:30 AM

Plugging Completed 6-27-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 4540'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	267'	None

RECEIVED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud.
Plugged with 50 sacks at 1120'; 40 sacks at 600'; 40 sacks at 300';
and 10 sacks at 40'. 15 sacks in rathold and 5 sacks in water well.
Used 60/40 Pozmix with 2% gel and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.


STERLING DRILLING COMPANY

(Signature) F. A. Wuellner

F. A. Wuellner, Secretary

(Address) P. O. Box 129, Sterling, Kansas

SUBSCRIBED AND SWORN TO before me this 28 day of June, 19 84



Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - HACKER #2-31

Located: NE NE NW, Section 31-24S-16W, Edwards County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 20, 1984

COMPLETED: June 27, 1984

TOTAL DEPTH: 4540'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 95 Surface Soil and Sand	Ran 6 joints new 8 5/8", 23# casing.
95 - 275 Clay and Shale	254.49' pipe set at 267' K.B. Cemented
275 - 730 Shale, Sand, Red Beds	with 210 sacks 60/40 Pozmix, 3% cc.
730 - 1114 Shale	Plug down at 3:00 AM, 6-21-84, by
1114 - 1126 Anhydrite	Halliburton.
1126 - 1504 Shales	
1504 - 4540 Lime and Shale	Plugged

Deviation Surveys: 1 1/2° at 1504'
1 1/2° at 4408'

RECEIVED
STATE CORPORATION COMMISSION

JUL 03 1984

CONSERVATION DIVISION
Wichita, Kansas