

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,237-0000

LEASE NAME Adams

WELL NUMBER 2-31

SPOT LOCATION NE NW SE

SEC. 31 TWP. 24 RGE. 16 (W)

COUNTY Edwards

Date Well Completed 12-11-84
10:00 PM,

Plugging Commenced 12-10-84

12:05 AM,
Plugging Completed 12-11-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 4515'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	309'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. Heavy mud plugged through open ended drill pipe.
50 sacks at 1110'; 70 sasks at 540'; bridge, sack hulls, plug and 10 sacks
at 40'; 15 sacks in rathole; 10 sacks in mousehole. Used 60/40 Pozmix,
plus 2% gel, total of 4%, and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

12-17-84

STATE OF KANSAS COUNTY OF RICE, ss. STATE CORPORATION COMMISSION

F. A. Wuellner (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

DEC 17 1984


CONSERVATION DIVISION

STERLING DRILLING COMPANY, Inc.

(Signature) F. A. Wuellner

F. A. Wuellner, Secretary

(Address) P. O. Box 129, Sterling, Kansas
67579



SUBSCRIBED AND SWORN TO before me this 11 day of December, 1984

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- ADAMS #2-31
 Located: NE NW SE, Section 31-24S-16W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 4, 1984

COMPLETED: December 11, 1984

TOTAL DEPTH: 4515'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 120 Surface Soil and Sand	Ran 7 joints new 8 5/8", 23# casing.
120 - 312 Shale	296.02' pipe set at 309' K.B.
312 - 1000 Lime and Shale	Cemented with 225 sacks 60/40 Pozmix, 3% cc. Plug down at 5:00 PM, 12-4-84, by Howco.
1000 - 1950 Shale	
1950 - 2000 Shale and Lime Stringers	
2000 - 4515 Lime and Shale	Plugged.

Deviation Surveys: 1° at 2181'
 2° at 4384'

RECEIVED
 STATE CORPORATION COMMISSION

DEC 17 1984

CONSERVATION DIVISION
 Wichita, Kansas