

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-047-21,128-0000

LEASE NAME Kearstin

WELL NUMBER 2-32

 Ft. from S Section Line

 Ft. from E Section Line
 SW NE SW

SEC. TWP. RGE. (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 10-8-87

Plugging Completed 10-20-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F.G. Holl Company

ADDRESS P.O. Box 780167
 Wichita, Kansas 67278-0167

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. # 1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4525'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	260'	none
				4-1/2"	4515'	3183'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped bottom with 50 sacks cement to 4200'. Shot pipe @3438', 3183', pulled a total of 77 joints of 4-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1987

James Stapp
 Notary Public - Commission

My Commission Expires:



OCT 29 1987

10-29-87

CONSERVATION DIVISION
 Wichita, Kansas

Form CP-4
 Revised 07-86

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- KEARSTIN #2-32

Located: SW NE SW, Section 32-24S-16W, Edwards County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 31, 1983

COMPLETED: November 6, 1983

TOTAL DEPTH: 4525'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 123 Surface Soil and Sand	Ran 6 joints new 8 5/8", 24# casing. 248.39' pipe set at 260' K.B. Cemented with 210 sacks 60/40 Pozmix plus 3% cc. Plug down at 4:30 PM, 10-31-83, by Howco.
123 - 263 Shale	
263 - 1105 Shale, Sand, Red Bed	
1105 - 1118 Anhydrite	Ran 112 joints 4 1/2", 10.5# casing. 12 joints were used. 4506.11' pipe set at 4515' K.B. Cemented with 100 sacks Lite and 125 sacks 50/50 Pozmix, plus our regular additives. Plugged rat hole and water well. Plug down at 8:00 AM, 11-6-83, by Howco.
1118 - 1065 Shale	
1065 - 4525 Lime and Shale	

Deviation Surveys: 1° at 2263'
1 3/4° at 4370'

STATE OF KANSAS DEPARTMENT OF REVENUE

STATE OF KANSAS DEPARTMENT OF REVENUE

SEP 23 1987

SEP 23 1987

STATE OF KANSAS DEPARTMENT OF REVENUE