

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

send to State
API NUMBER 15-047-21400-0000

LEASE NAME WOOD G

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER _____

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 32 TWP. 24 SRGE. 16W (E) or (W)

COUNTY Edwards

LEASE OPERATOR OIL PRODUCERS, INC OF KANSAS

ADDRESS P O BOX 8647, WICHITA KS 67208

PHONE (316) 681-0232 OPERATORS LICENSE NO. 8061

Date Well Completed 09-24-94

Plugging Commenced 5:15 A.M.
09-24-94

Character of Well _____

Plugging Completed 7:00 A.M.
09-24-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 22, 1994 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? YES

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Plugged with 50 sacks at 1120', 50 sacks at 700', 50 sacks at 300', 10 sacks at 40', and 15 sacks in rathole. 60/40 Poz 6% Gel.

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P O BOX 129, STERLING KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OIL PRODUCERS INC OF KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead
Richard L. Mead

(Address) P O BOX 129, STERLING KS 67579

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1994

Cheryl R. Davis
Notary Public

My Commission Expires: 02-15-97

USE ONLY ONE SIDE OF EACH FORM



Form C-1
Revised 05-88

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1994
WICHITA, KANSAS

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- WOOD G

Located: 110' S of NE NE NW of Sec. 32-24S-16W,
Edwards County, Kansas

OWNER: OIL PRODUCERS, INC OF KANSAS

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: September 19, 1994

COMPLETED: September 24, 1994

TOTAL DEPTH: 4400' Driller

LOG

0' - 165' Surface Soil and Sand
165' - 265' Red Bed
265' - 560' Red Beds and Shales
560' - 4350' Lime and Shale
4350' - 4400' Chert Lime and Shale

CASING RECORD

Spud at 7:15 AM, 09-19-94. Drilled 265' of 12 1/4" hole. Ran 6 joints 8 5/8" surface casing. 248.99' set at 260' K.B. Cemented with 200 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 11:45 AM by Allied, ticket #6927. Good returns.

Plugged.

DEVIATION SURVEY

1/2° @ 265'

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1994

WICHITA DIVISION
WICHITA, KANSAS