


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County. Sec. 29 Twp. 24S Rge. 18 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
SE SW NW

Lease Owner Alpine Drilling Company
Lease Name Southwestern College #1 Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plat

Date Well completed January 28, 1977 19
Application for plugging filed January 28, 1977 19
Application for plugging approved January 28, 1977 19
Plugging commenced 9:00 AM, January 28, 1977 19
Plugging completed 12:30 PM, January 28, 1977 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4689'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	279'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Pumped thru open end Drill Pipe
40 sacks at 540' and 35 sacks at 300'
and solid bridge with plug and 1/2 sacks hulls
at 40' with 12 sacks to surface, 3 sacks in
rathole. Used 50/50 Pozmix cement.

RECEIVED
FEB 03 1978
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. **STERLING DRILLING COMPANY**

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and sworn to before me this 30th day of January, 19 78

My commission expires _____



Bernard Laudermilk
Bernard Laudermilk, Notary Public.



STERLING DRILLING COMPANY
 P. O. Box 129
 Sterling, Kansas 67579

WELL LOG - - - - - SOUTHWESTERN COLLEGE #1
 Located: SE SW NW, Section 29-24S-18W, Edwards County,
 Kansas

OWNER: Alpine Drilling Company
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 17, 1978
 COMPLETED: January 23, 1978

TOTAL DEPTH: 4689'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 165 Clay and Sand	Ran 7 joints used 28" 5/8" casing, 268.39' set at 279' K. B. with 250 sacks Common with 2% gel and 3% cc. Plug down at 7:45 PM, 1-17-78, by Allied.
165 - 385 Shale	
385 - 1274 Shale and Red Beds	
1274 - 1280 Shale and Anhydrite	
1280 - 1795 Shale	
1795 - 4526 Lime and Shale	
4526 - 4542 Cherty Lime and Shale	
4542 - 4562 Chert (Miss.)	
4562 - 4600 Sand and Chert	
4600 - 4689 Lime and Shale	Plugged.

RECEIVED
 FEB 03 1978
 STERLING DRILLING COMPANY
 Sterling, Kansas