



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herrman ^{Triple} ~~of Triple~~ Mr. Dutton D Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Herrman guarantees payment of the plugging fee.

Operator's full Name: Triple ~~Triple~~ Mr. Dutton D Drlg Co.

Complete Address: 2707 N. Madison Hutchinson, Ks

Lease Name: Casley Well No. 1

Location: 330 ft. WL-660 ft. SL- ^{SW/SW} Sec. 1 Twp. 28 Rge. 5 (E)(W) W

County: Kingman Total Depth 3860 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Herrman was instructed to plug the well as follows:

210 ft of 8 5/8 surface pipe cemented with 200 sacks--
circulated. Fill hole to 200 ft., 1/2 sack hulls, plug, 25
sacks cement. Mud to 40 ft., 1/2 sack hulls, plug, 10 sacks
cement to surface. 2 sacks cement in rat hole.

Very truly yours,

A. Russell Robertson
Conservation Division Agent