

15095-01758-0000

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 15 1965
 09-15-65
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

August 25, 1965.

Dear Sir:

Mr. Ralph Watson of Knight Caseing Pulling Co has this
 date requested permission to plug the following described well:

Mr. Ralph Watson guarantees payment of the plugging fee.

Operator's full Name: Shallow Water Refining Co.

Complete Address: 1325 Wichita Plaza, Wichita, Kansas.

Lease Name: Bartholomew Unit Tract Well No. #17 - 3

Location: NW-NE-NE Sec. 1 Twp. 28 Rge. 5W (E) (W)

County Kingman Total Depth 3789: Oil Well x

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Watson was instructed to plug the well as follows:

3770' of 5 1/2" 516mg string open hole. Sand to 3760' & 5 sacks
cement. 199' of 8 5/8" surface pipe circulated with 135 sacks
cement. Hole filled to 180' with mud, 10' rock bridge & 25
sacks cement. Hole filled to 40' with mud, 10' rock bridge
& 10 sacks cement to base of cellar. Cap welded on surface pipe

Very truly yours,

Walter Justice
 Conservation Division Agent