



15-095-20885-0000

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
WILLIAM G. GRAY  
JAMES B. DOUGLAS

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Clyde Kuhn of Graves Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Court Graves guarantees payment of the plugging fee.

Operator's full Name: Graves Drilling Co., Inc.

Complete Address: 910 Union Center, Wichita, Kansas 67202

Lease Name: Viney Well No. 1-A

Location: C S/2 SE SE Sec. 8 Twp. 28S Rge. 5W (E)(W)

County: Kingman Total Depth 3880' Oil Well

Gas Well  Input Well  SWD Well  D. & A.  Lost Hole

Mr. Kuhn was instructed to plug the well as follows:

Fill hole with heavy mud to 210'. Pump 40 sacks of cement through  
drill pipe with pump truck. Push plug and 1/2 sack hulls to 40' and  
pump 12 sacks of cement through drill pipe with pump truck to base of  
well cellar. Plug rat hole with 3 sacks of cement.

Very truly yours,

*RWD*  
*04-00-110*  
*11-10-79*

*Frank [Signature]*  
Conservation Division Agent