

To: **1 040892**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-30

API NUMBER 15-185-22,934-0000  
C NW SW, SEC. 36, T 7 S, R 11 W.  
1980 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30080

Lease Name McComb Well # C-2  
County Stafford

Operator: Honey Oil Co., Inc.  
Name:  
Address 401 E. Douglas  
Wichita, KS 67202

Well Total Depth 3950 128.37 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 229

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 30 Month: 9 Year: 19 94  
Plugging proposal received from Richard McIntyre

(company name) Kelso Casing Pulling (phone) 316-938-2943  
wells: 5 1/2" at 3945' w/125 sx cement, Perfs at 3814-36'

1st plug sand back to 3760' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
10 3/4" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3:15 p.m. Day: 30 Month: 9 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 3760' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement. Maximum pressure 1000 psi and shut in 700 psi.  
8 5/8" collar welded in top of 10 3/4" surface pipe.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 04 1994

Remarks: Used 60/40 Pozmix 6% gel by United. Recovered 2606' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

I (did / did not) observe this plugging.

DATE 10-6-94

REV. NO. 41328

Signed Stephen J. Pfeiffer  
(TECHNICIAN)