

1-30-84 No Logging

1080120

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,957-0000

SW SE NE, Sec. 35, T 24 S, R 11 W

2310 feet from N/section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9372

Lease Name Paulsen Well # 1-35

Operator: Louis Kapp - d/b/a/ Kapp Co.
Name & 18 Carnation Drive
Address Belleville, IL 62221

County Stafford

Well Total Depth 4100 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 255

133.25

618

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 7:30 am Day: 20 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Steve Feller

(company name) Wheatstates (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4082' with 30 sx cement

2nd plug at 700' with 50 sx cement

3rd plug at 300' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement. Plug water well with 5 sx cement

Signed J. A. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:00 am Day: 20 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4082' with 30 sx cement, 2nd plug at 700' with 50

sx cement, 3rd plug at 300' with 40 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 15 sx cement. Plug water well with 5 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Buie

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

Signed J. A. Metz (TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 4-4-84

INV. NO. 1050

3-20