

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21375-00-00
Spot: W2NENE Sec/Twnshp/Rge: 36-24S-17W
4620 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: WHEATON Well Number: 1-36
County: EDWARDS Total Vertical Depth: 4560 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 6427 EAST KELLOGG
WICHITA, KS 67207

Conductor Pipe: Size _____ feet: 8 1/4 8.20
Surface Casing: Size 8.625 feet: 315 WITH 225 SX CMT
Production: Size 4.5 feet: 4556 WITH 225 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2001 4:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SAND BACK TO 4325' & 4 SX CMT. 1ST PLUG AT 1150' WITH 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/01/2001 5:40 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 4535'. PERFS AT 4382-4386'. SAND BACK TO 4325' & 4 SX CMT ON TOP. PUMP 15 SX GEL. 1ST PLUG AT 1150' WITH 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2218' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED

NOV 05 2001

KCC WICHITA

INVOICED

NOV 02 2001

DATE 11-5-01

INV. NO. 2002060909