

8-9

2-100619

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-155-20,460-0000

C N/2 NW SW, SECTION 26 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5271 2310 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR S & K Oil Company
NAME & RR #1, Box 99
ADDRESS Burrtion, KS 67020

LEASE NAME: Goering #A-11
COUNTY: Reno 115.86
WELL TOTAL DEPTH: 3565' CIBP 3450'
PIPE: 5-1/2" @ 3565'
PIPE: 8-5/8" @ 546'/100 sx
SURFACE CASING: 10-3/4" @ 253'/285 sx

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A
OTHER WELL AS HEREINAFTER INDICATED: perf 3354-64' 3308-14'

PLUGGING CONTRACTOR: Gressel Oilfield Service
ADDRESS: Box 607, Burrtion, KS 67020 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 10:00a DAY: 9 MONTH: 8 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Ed Gressel
COMPANY NAME: Gressel Oilfield Services PHONE: 316-463-5161

WERE: Sand 50' above perfs or open hole & dum 6 sx cmt
w/bailer - shoot & pull pipe - run tub to 650' -
spot 35 sx cmt - pull tub to 300' - circ to surf.

PLUGGING PROPOSAL RECEIVED BY: Merlan Unruh

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()
COMPLETED: HOUR: 11:30 DAY: 9 MONTH: 8 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded to 3100' & dumped 6 sx cmt w/bailer - shot &
pulled 2255' of 5-1/2" - ran tub to 630' & spotted 35
sx cmt - pulled tub to 300' & circ to surface w/98 sx
cmt - fell 120' - refilled w/2 yds slurry mix.

REMARKS: Howco #015702 40/60 total 4% gel Haven Redimix #9819

I DID OBSERVE THIS PLUGGING.

RECEIVED

STATE CORPORATION COMMISSION

INVOICED

AUG 21 1990

DATE: 8-29-90

CONSERVATION DIVISION
WICHITA, KANSAS

J. L. Sanders
J. L. Sanders (AGENT)

FORM CP-2/3
REV. 3/90

[Handwritten mark]