

2 040175

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-095-20765-000

NELSE, SEC. 23, T. 27 S., R. 10 (W)E

1980 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047

Lease Name McMichael Well # 1

Operator: Rupe Oil Co.

County Kingman 85.15

Name & Address Bx 2273

Well Total Depth 2620 feet

Wichita KS 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size ~~8 3/8~~ feet 2469 30/1

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gallaughier Well Service License Number 8752

Address Bx 100 Isabel Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from John

(company name) Gallaughier Well Service (phone) _____

were: _____

4 1/2 2469 Sand back to 2300' & 4 SKS.

Perf. 2352-62 3H 15G 120 60/40 3 1/2.

Rec 1800

Plugging Proposal Received by Steve A. Sun
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1035 Day: 6 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT This well was sand back to 2300'

and 4 sacks of cement was dumped, tailed on top of
sand, to cover off the perforations. The pipe was shot
off and approximately 1800' of 4 1/2 was recovered. The
top was squeezed down the 8 3/8" casing by pumping
3000 lbs of bull, 15 sk of Gel and 120 pipe of 40/40.

Remarks: Howco 083112 MX750 SI 450
(If additional description is necessary, use BACK of this form. MAR 13 1985)

INVOICED (did, not) observe this plugging.

DATE 3-13-85
INV. NO. 7337 3-6

Signed Steve A. Sun
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas