

10-27

RECEIVED
KANSAS CORPORATION COMMISSION

2-040779

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 207B
Wichita, Kansas 67202

NOV 29 1994

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-095-20,794-0001

C NE NW, SECTION 23 TOWNSHIP 27 RANGE 10W
4620

OPERATOR LICENSE # 6153

3300 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR CHEW O&G COMPANY
NAME & P O BOX 90
ADDRESS LYONS KS 67554

LEASE NAME: MURPHY #1 OWWO
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4404' 143.13

PIPE: _____

SURFACE CASING: 8-5/8" @ 218'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKES CASING PULLING
ADDRESS: CHASE KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: MANNY
COMPANY NAME: MIKE'S CASING PULLING PHONE: _____

WERE: 5-1/2" @ 4393 - PERFS 4026-36' - SAND TO 3975' & 5 SX
- 35 SX CMT 1350' - 35 SX CMT CIRC 260' TO SURF

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: 1215 DAY: 27 MONTH: 10 YEAR: 1994

ACTUAL PLUGGING REPORT:

SAND DUMPED DWN 5-1/2" CSG TO COVER THE PERFORATIONS
- TOP OF SAND AT 3950' & CAPPED W/5 SX CMT - 5-1/2"
RECOVERED FROM 3500' & PULLED TO 1370' & 35 SX CMT
SPOTTED - PIPE PULLED TO 980' & 35 SX SPOTTED - PIPE
PULLED TO 280' WHERE CMT WAS CIRC TO SURF.

REMARKS: ALLIED 60/40 4%

I DID OBSERVE THIS PLUGGING

INVOICED
DATE 12-5-94
INV. NO. 41794


Steve Van Gieson (AGENT)

DW