

2-070657

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

11-15

API NUMBER: 15-095-21,663-0000

NW NW NW, SECTION 24 TOWNSHIP 27 RANGE 10W

OPERATOR LICENSE # 30146 4950 FEET FROM S SECTION LINE  
OPERATOR MACH PETROLEUM INC 4950 FEET FROM E SECTION LINE  
NAME & P.O. BOX 35583  
ADDRESS TULSA, OK 74153  
LEASE NAME: BAYER #7  
COUNTY: KINGMAN 144.95  
WELL TOTAL DEPTH: 4460'  
PIPE: 5 1/2" @ 4459'  
SURFACE CASING: 8 5/8" @ 313'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: CLARK CORPORATION  
ADDRESS: P.O. BOX 187, MEDICINE LODGE, KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 15 MONTH: 11 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: STEVE BUNDY  
COMPANY NAME: MACH PETROLEUM INC PHONE: (316) 596-2676  
WERE: CIBP 3875'  
35 SACKS AT 1400'  
35 SACKS AT 950'  
300' - 0'

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 25 1996

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL {  } PART {  } NONE {  } WICHITA, KS

CONSERVATION DIVISION  
WICHITA, KS

COMPLETED: HOUR: 4:00 DAY: 15 MONTH: 11 YEAR: 1996

ACTUAL PLUGGING REPORT: SET CIBP AT 3875' AND 2 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2200'. PULLED TO 1400', PUMPED 35 SACKS. PULLED TO 950', PUMPED 35 SACKS. PULLED TO 300', CIRCULATED CEMENT SURFACE. CEMENT FELL 30'. READY MIXED TO SURFACE.

REMARKS: 60/40 POZ 4% GEL HALLIBURTON

INVOICED

DATE 11-25-96  
INV. NO. 47047

I DID OBSERVE THIS PLUGGING.

Jack Luthi  
JACK LUTHI  
FORM CP-2/3  
REV. 3/90