

2040176

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C

API NUMBER 15-095-20805-0000

SW/NW, SEC. 24, T 27 S, R 10 W/E

4620 3300 feet from N (S) section line

3300 4620 feet from W (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047

Lease Name Bayer Well # 1

Operator: Rupe Oil Co

County Kusman 80.44

Name & Address Bx 273

Well Total Depth 2475 feet

Wichita Ks.
67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gallaugher Well Service License Number 8752

Address Bx 100 Isabel Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from John

(company name) Gallaugher Well Service (phone) _____

were: Sand Back 2330' @ 4 SFs

PBTD 2415 3H 15G 115 60/40 3% cc

4 1/2 2464

Perf 2380-90

RECEIVED

MAR 13 1985

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Stella Gusev
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1115 Day: 8 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Sand was dumped down the 4 1/2 to cover
off the perforations. Top of the sand was approximately 2330'
and 4 sacks of cement was dump on top of the sand. The 4 1/2
was shot off and 1800' was recovered. The top was plugged
by squeezing thru the 8 5/8 3 sacks of Hall's, 15 sacks of Ciel
and 115 60/40 3% cc

Remarks: HOWCO 083183 MX 500# SI 250#
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 3-13-85

Signed Stella Gusev
(TECHNICIAN)

INV. NO. 7338
3-8