

2 040174

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-20816-0000

1/2 W C 1/4 NW 1 SW, SEC. 24, T 27 S, R 10 W

1980 feet from N 1/4 section line

4620 feet from W 1/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047

Lease Name Dostal Well # 2

Operator: Rupe Oil Co.

County Kinsman 81.58

Name & Address PO Box 2273

Well Total Depth 2510 feet

Wichita Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gallaugher Well Service License Number 8752

Address Bx 100 Isabel Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from John

(company name) Gallaugher Well Service (phone) _____

were: _____

4 1/2 2500 Sand Back to 2330 & 4 1/2 K RECEIVED

Perf. 2356-62 3H 15' 6 115 60/40 30/10 STATE CORPORATION COMMISSION

Rec 1800 MAR 13 1985

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Crum
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1500 Day: 4 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT This well was sandbed back to cover off the perforations. The top of the sand was approximately 2330' and 4 sacks of cement was dump tailed on top of the sand. The 4 1/2 was shot off and 1800' of pipe was removed. The top was squeezed thru the 8 5/8 by pumping 3 sacks of Halls, 15 sacks of gel and 120' sack of 140 Pz.

Remarks: HOWCO 083201 MX 400 SI 200'
(If additional description is necessary, use BACK of this form.)

(I did / did not) observe this plugging.

DATE 3-13-85

INV. NO. 7339

Signed Steve Crum
(TECHNICIAN)