

12-13

2-040667

202
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-095-20674-000

200' W SE SE NW, SECTION 4 TOWNSHIP 28 RANGE 5W

OPERATOR LICENSE # 5151 2970 ~~2070~~ FEET FROM S SECTION LINE
3170 ~~2970~~ FEET FROM E SECTION LINE

OPERATOR Gear Petroleum Company, Inc.
NAME & 125 North Market, #1075
ADDRESS Wichita, KS 67202

LEASE NAME: Johnson #1

COUNTY: Kingman

WELL TOTAL DEPTH: 3795' 123.33

CONDUCTOR PIPE: " @ ' "

SURFACE CASING: 8-5/8" @ 213'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Gressel Oilfield Service
ADDRESS: Burton, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: X MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Butch Hoberecht
COMPANY NAME: Gear Petroleum PHONE: _____

WERE: 4-1/2" 1840' - PBD 1840' - Perf 1761-69' - sand to
1700' & 4 sx - 35 sx 737' - circ 300'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 1200 DAY: 13 MONTH: 12 YEAR: 1991

ACTUAL PLUGGING REPORT:
Perforations were covered with sand to 1700' & capped
w/4 sx cmt - 4-1/2" csg shot loose at 737' - 35 sx cmt
plug spotted at 737' - 4-1/2" csg pulled to 300'
circ to surface. Recovered 737'

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: Allied Cmt #2630 60/40 DEC 26 1991

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 1-10-92

INV. NO. 34290

Steve Van Gieson
Steve Van Gieson (AGENT)

CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3
REV. 3/90