

2-040819

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

10-5

API NUMBER: 15-095-20,736-0000
50'S,NE,SE,SE, SECTION 05 TOWNSHIP 28 RANGE 05W

OPERATOR LICENSE # 31142 940 FEET FROM S SECTION LINE
990 FEET FROM E SECTION LINE

OPERATOR PETROLEUM PROPERTY SERVICES, INC.
NAME & 155 N. MARKET, #1010
ADDRESS WICHITA, KS 67202

LEASE NAME: RAMSDALE #2
COUNTY: KM
WELL TOTAL DEPTH: 1790 PB 1771'

58.18

PIPE: _____

SURFACE CASING: 8 5/8" @ 209'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: GRESSEL CORP.

ADDRESS: BURTON, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: BUTCH HOPERECHT

COMPANY NAME: P.P.S.I. PHONE: _____

WERE: 4 1/2" @ 1789', SAND TO 1690' & 4 XS. PERF. @ 1744-
66' REC PIPE 35 XS. @ 825', 35 XS. @ 450' CIRC. CMT. @
250'.

PLUGGING PROPOSAL RECEIVED BY: JERRY CLARK

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { _____ } PART { X } NONE { _____ }

COMPLETED: HOUR: 15:00 DAY: 5 MONTH: 10 YEAR: 1995

ACTUAL PLUGGING REPORT:

THE PERF WERE COVERED WITH SAND FROM 1790' TO 1690'
AND CAPPED WITH 4 XS. OF CMT. THER 4 1/2" WAS RECOVERED
FOR 1200' AND PULLED TO 830' WHERE 35 XS. OF CMT. WAS
SPOTTED. THE 4 1/2" WAS PULLED TO 450' WHERE 35 XS. OF
CMT. WAS SPOTTED. THE 4/2" WAS AGAIN PULLED TO 260'
WHERE CMT. WAS CIRC. TO SURFACE. THE REMAINING CASING
WAS PULLED OUT AND THE CMT. WAS TOPPED OFF.

REMARKS: ALLIED CMT. 60/40 4% GEL.

I DID OBSERVE THIS PLUGGING.


Steve Van Gieson (AGENT)

INVOICED

DATE 11-1-95
INV. NO. 43920

FORM CP-2/3
REV 3/90
RECEIVED
KANSAS CORPORATION COMMISSION

OCT 26 1995

CONSERVATION DIVISION
WICHITA, KS

Dec