

2 050393

15-095-19128-0001

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA

C NE NW, SEC. 9, T 28 S, R 5 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5783

feet from S section line

feet from E section line

Operator: Galloway Drilling Co., Inc.
Name &
Address 340 Broadway Plaza Building
105 S. Broadway
Wichita, KS 67202

Lease Name Padgett Well # 4 SWD

County Kingman 124.02

Well Total Depth 3816 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 161

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Gressel Corp. License Number

Address Haysville, KS

Company to plug at: Hour: 8 a.m. Day: 16 Month: 6 Year: 19 86

Plugging proposal received from

(company name) (phone)

were: 5 1/2" casing set at 3800' open hole to 3816' - sand back to 3750' and dump 6 sacks
of cement - shoot pipe and pull

redi mix 250' to surface

Plugging Proposal Received by Warren Kirkpatrick
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:30 Day: 17 Month: 6 Year: 19 86

ACTUAL PLUGGING REPORT Sanded back to 3700 feet and dumped 6 sacks of cement. Shot 5 1/2"
off at 295 feet. Dropped 7 7/8" rotary bit on top of 5 1/2" stub, then dumped 10 gallons
of rock and sand and filled to surface with redi mix.

RECEIVED
STATE CORPORATION COMMISSION

Remarks:

JUN 25 1986 06-25-86

(If additional description is necessary, use BACK of this form.)

INVOICED

JUN 25 1986

DATE

INV. NO.

14206

Signed

(TECHNICIAN)