

LEASE NAME RAMSDALE

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

940 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR PETROLEUM PROPERTY SERVICES, INC.

SEC. 5 TWP. 28 RGE. 5 (E) or (W)

ADDRESS 155 N. MARKET, SUITE 1010, WICHITA, KS 67202

COUNTY KINGMAN

PHONE#(316) 265-3351 OPERATORS LICENSE NO. 31142

Date Well Completed 8/14/78

Character of Well GAS

Plugging Commenced 10/5/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/5/95

The plugging proposal was approved on 10/03/95 (date)

by STEVE VANGIESON (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation INDIAN CAVE Depth to Top 1744 Bottom 1766 T.D. 1790

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
INDIAN CAVE	GAS	1744	66	8 5/8 4 1/2	209 1789	NONE 1200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
DUMP SAND TO 1690, 5 SX CEMENT 1690 TO 1610. SHOT PIPE AT 1200' AND PULL UP TO 825'. SPOT 35 SX APPROX 825 TO 650, PULL TO 450 AND SPOT 35 SX APPROX 450 TO 270. PULL UP TO 250 AND CIRCULATE CEMENT TO SURFACE. FINISH PULLING CASING AND FILL TOP WITH 5 SX

Name of Plugging Contractor PETROLEUM PROPERTY SERVICES, INC. License No. 31142

Address 155 N. MARKET, SUITE 1010, WICHITA, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PETROLEUM PROPERTY SERVICES, INC.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

R. J. THATCHER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) R. J. Thatcher

(Address) SAME AS ABOVE

RECEIVED
KANSAS CORPORATION COMMISSION



SUBSCRIBED AND SWORN TO before me this 18TH day of OCTOBER, 19 95

OCT 18 1995

Rosann M. Schippers
Notary Public

CONSERVATION DIVISION
WICHITA, KS My Commission Expires: 9-28-99
USE ONLY ONE SIDE OF EACH FORM