

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-21,228-000

LEASE NAME Clause #1

WELL NUMBER _____

SPOT LOCATION C NW NE

SEC. 7 TWP. 28 SRGE. 5w (E) or (W)

COUNTY Kingman

Date Well Completed _____

Plugging Commenced 12/9/85

Plugging Completed 12/18/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Lochiel Exploration

ADDRESS 1200 Sunlife Plaza-N. Tower, 140-4th Ave SW, Calgary, Alberta

PHONE # () _____ OPERATORS LICENSE NO. 7283

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4275'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	266'	none
				4 1/2"	4277'	2838'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom was already plugged off. Killed well with 110 bbls salt water. Pull 631' tubing, cement with 35 sacks 60/40 poz 6% gel & displace to bottom 3617'. Shot pipe at 3065', 2972', and 2838'. Pulled 67 joints of pipe. Plugged well with 3 hulls, 15 gel, 60 cement, released plug, & 60 sacks 60/40 poz 2% gel.
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 7th day of January, 1986

My Commission expires:



Irene Hoover
Notary Public

Form CP-4
Revised 01-84