


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-095-01731-0000  
WELL PLUGGING RECORD

Kingman County, Sec. 8 Twp. 28 Rge. 5 (E)W (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE  
Lease Owner Morgenstern Oil Operations  
Lease Name Viney "B" Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 12-4-61 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 12-6-61 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Fred Hample  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3800 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8-5/8"	146'	None
				5-1/2"	3794'	3501'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3800', ran sand to 3775' and dumped 5 sacks of cement @ 3775' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 260', set rock bridge to 250' and filled with ready-mix from 250' to base of cellar.

PLUGGING COMPLETE.

STATE CORPORATION COMMISSION

JAN 25 1962  
01-23-62

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KKS KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 61

My commission expires May 20, 1964

Milton J. Tolson  
Notary Public.



15-095-01731-0000

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK -- WICHITA, KANSAS

COMPANY D. J. BRIMS et al

SEC. 8 T. 28 R. 5W

FARM Viney "B"

NO. 2

LOC. NE SE SE

TOTAL DEPTH 3800

COMM. 12-2-50

COMP. 12-19-50


SHOT OR TREATED

CONTRACTOR Pabco Drilling, Inc.

ISSUED 3-10-51

COUNTY Kingman

KANSAS



CASING

8 5/8" 11.5' cem. w/100 sx

5 1/2" 3794' cem. w/50 sx

ELEVATION

PRODUCTION I.P.P. 24 1/2 BOPD  
1,500,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

shale & shells	50
shale	280
shale & shells	725
lime & sand	700
lime & shale	945
iron, lime & shale	985
lime & shale	1115
lime	2959
lime & shale	3523
lime	3700
Total Depth	

Scout Tops:

Lansing	2969
Mississippi Chert	3770
Mississippi Dolomite	3795

Ctr. @ 3770, 3780, 3790,  
3800 & DST

RECEIVED  
STATE CORPORATION COMMISSION

DEC 5 1961  
CONSERVATION DIVISION  
Wichita, Kansas