

1509520885000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 8 Twp. 28 Rge. 5 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C S/2 SE SE

Lease Owner Graves Drilling Co., Inc/
Lease Name Viney Well No. I-A
Office Address 910 Union Center, Wichita, Ks. 67202

Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plat

Date Well completed 10-14-79 19
Application for plugging filed 10-14-79 19
Application for plugging approved 10-14-79 19
Plugging commenced 10-14-79 19
Plugging completed 10-14-79 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3880
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 210'. Pumped 40 sacks of cement through drill pipe with pump truck. Pushed plug and 1/2 sack hulls to 40' and pumped 12 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 3 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Court Graves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Court Graves
910 Union Center, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 79

My commission expires May 1983
STATE CORPORATION COMMISSION

Rebecca L. Matthews
Notary Public.

NOV 01 1979
CONSERVATION DIVISION
Wichita, Kansas

15-095-208850000

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc. OPERATIONS COMMENCED: 6 October 1979
 910 Union Center
 Wichita, Kansas 67202.

CONTRACTOR: Graves Drilling Co., Inc. OPERATIONS COMPLETED: 14 October 1979
 910 Union Center
 Wichita, Kansas 67202

CASING RECORD: 5 Jts. 206' of used 8 5/8" LOCATION: Viney 1-A
 cemented with 185 sacks C S/2 SE SE
 Section 8-28S-5W
 Kingman Co., Kansas

0 - 10 Sand
 10 - 206 Red bed
 206 - 310 Red bed and sand
 310 - 843 Red bed
 843 - 1325 Red bed and lime
 1325 - 1610 Shale and lime
 1610 - 1755 Shale and lime and sand
 1755 - 3817 Shale and lime
 3817 - 3880 Shale
 3880 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Court Graves
Vice-President

STATE OF KANSAS)
SEDGWICK COUNTY) SS:

Subscribed and sworn to before me, a Notary Public, this 24th day of October, 1979

My Commission Expires: 17 May 1983

Rebecca L. Matthews
Rebecca L. Matthews

RECEIVED
STATE CORPORATION COMMISSION

NOV 01 1979

CONSERVATION DIVISION
Wichita, Kansas

[Handwritten notes and signatures]