


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Kingman County. Sec. 10 Twp. 28s Rge. 5 (E) (W)  
Location as "NE/CNWxSWx" or footage from lines SW SE SE  
Lease Owner Faulconer and McCoy  
Lease Name Turner Well No. 1  
Office Address 336 Union Center Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-18-65 19  
Application for plugging filed 10-18-65 19  
Application for plugging approved 10-18-65 19  
Plugging commenced 10-18-65 19  
Plugging completed 10-18-65 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	221'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 220' 1/2 sack hulls 2 sacks dry cement plug and 23 sacks cement  
Mud to 40' 1 sack dry cement 1/4 sack hulls plug and 9 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

OCT 22 1965

CONSERVATION DIVISION  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling Inc.  
Address Box 486 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
Box 486 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of October, 1965

My commission expires April 1, 1967

Glenda D. [Signature]  
Notary Public.

DRILLER'S LOG

COMPANY: Faulconer and McCoy  
 CONTRACTOR: LEBEN DRILLING, INC.  
 Farm: Turner #1  
 Location: SW SE SE Sec. 10-28s-5W  
 Kingman County, Kansas  
 COMMENCED: 10-9-65  
 COMPLETED: 10-18-65

0 20 Surf Sand and Clay  
 20 75 Shale  
 75 221 Red Bed  
 221 710 Shale and Shells  
 710 1247 Shale and Lime  
 1247 1700 Lime and Shale  
 1700 3155 Shale and Lime  
 3155 3260 Lime and Shale  
 3260 3805 Lime  
 3805 3855 Mississippi  
 3855 3900 Lime  
 3900 3900  
Rotary Total Depth - D & A

RECEIVED  
 STATE COMMISSION FOR CONSERVATION  
 OCT 22 1965  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" used Casing @ 221. cemented with 175 sks - 60/40 Pozmix  
 Sunset with 1/2% Gel. Cement circulated.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Turner #1 well, located SW SE SE of Section 10, Township 28 South, Range 5 West, Kingman County, Kansas, as reflected by the files of Leben Drilling, Inc.

*Leslie Kite*  
 \_\_\_\_\_  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 21th day of October, 1965.

*Ulanda Nichols*  
 \_\_\_\_\_  
 Ulanda Nichols

My Commission Expires  
 April 1, 1967