

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

15-095-21106-0000

COUNTY Kingman SEC. 10 TWP. 28 RGE. 5 ~~NE~~ W  
 Location as in quarters or footage from lines:  
E/2/SE/NE


Lease Owner Woodman & Iannitti Oil Company  
 Lease Name Twitmeier Well No. #1  
 Office Address Box 308 - Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced November 6, 1982  
 Plugging completed November 18, 1982  
 Reason for abandonment of well or producing formation  
Depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3845'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	247'	NONE
				4 1/2"	3844'	3083.45'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Dumped sand to 3700' and four (4) sacks cement.  
Shot pipe @ 3165' and 3070'.  
Pulled seventy-seven (77) joints of 4 1/2" casing.  
Squeezed well with six (6) sacks hulls, sixteen (16) sacks  
gel, one hundred thirty (130) sacks cement with 3% calcium  
chloride, shut in at 500 psi


RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 10 1982  
 CONSERVATION DIVISION  
 Wichita Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Kansas  
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 9th day of Dec., 19 82



Margaret Prosser  
 Notary Public.

My Commission expires: