

15-095-01478000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Kingman County, Sec. 10 Twp. 28S Rge. 5 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE NE NE

Lease Owner Beardmore Drilling Co.

Lease Name WULF Well No. 1

Office Address 603 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-19 1954

Application for plugging filed 12-19 1954

Application for plugging approved 12-19 1954


Plugging commenced 12-19 1954

Plugging completed 12-19 1954

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruell Durkee

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Soil		0	20			
Sand		20	40			
Red Rock & Shale		40	160	8-5/8"	160'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud 160' to 3850'

Wood Plug @ 160'

15 sacks Cement 115' to 160'

Heavy mud 30' to 115'

Wood Plug @ 30'

5 sacks Cement 0' to 30'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Co.

Address 603 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Heber Beardmore, Jr. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

(Address)

SUBSCRIBED AND SWORN to before me this 22 day of December, 1954

Leonard P. Toll

Notary Public.

My commission expires January 28, 1956

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 - 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE NO. 10-28-54
BOOK PAGE 86 LINE 38

15-095-01478-0000

WULF #1

SE NE NE, Sec. 10-28S-5W
Kingman County, Kansas

Drilled for: Beardmore, Sutton, and
Drilled by: Beardmore. Walgreen

Casing Record:

160' of 8-5/8" w/110 sacks

Drilling Commenced: 12/6/54
Drilling Completed: 12/20/54

Elevation: KB 1423
DF 1420
Gr. F 1418

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
R. Rock & Shale	160
Shale	390
Shale & Lime	910
Shale & Lime	1300
Shale & Lime	2010
Shale & Lime	2655
Shale & Lime	3075
Shale & Lime	3235
Lime	3385
Lime	3585
Shale & Lime	3785
Coring	3820
Lime & Chert	3845
Total Depth	3850
<u>TOPS:</u>	
Lansing	2962
Mississippi	3773
Chert	3773-85

CORE #1: 3785-3805; Recovered 20'; 6' green shale w/chert nodules
7' chert, chalky some shale, 7 limestone
fossiliferous, coarse crystalline, no show, no
porosity

CORE #2: 3805-3820; Recovered 15' shale & Limestone, trace oil
stain 3817-3819.

DST #1: 3795-3820; Open 1 hour, gas in 45 minutes, too weak to gauge;
shut in 15 minutes, recovered 120' gas cut mud with
few oil specks and 30' gas cut mud slightly oil cut.

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

RECEIVED
STATE COMMISSIONER OF GEOLOGY
CONSERVATION DIVISION

I, the undersigned, being duly sworn on oath state that the above and
within statement is a true and correct record and log of the well drilled
on the location above described, to the best of my knowledge and ability.

Heb Beardmore

Subscribed and sworn to before me this 22 day of December, 1954.

Leonard P. Tolle
Notary Public

My Commission Expires:
January 28, 1956

PLUGGING
FILE SEC 10 28 25W
PAGE 86 LINE 38