


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 10 Twp. 28S Rge. 11 (E) 5W (W)
Location as "NE/CNW%SW%" or footage from lines SW SW SE
Lease Owner Musgrove Drilling Company
Lease Name TURNER Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed November 12, 1961
Application for plugging filed verbally November 11, 1961
Application for plugging approved verbally November 11, 1961
Plugging commenced November 12, 1961
Plugging completed November 12, 1961
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well Fred Hampl, Pretty Prairie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3887' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	241	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 240' w/ 1/4 sk hulls & 40 sx cement
Set 2nd plug at 40' w/ 1/4 sk hulls & 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1961 11-28-61

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Drilling Company
Address 801 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers

801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of November, 1961

Leah Faye Hefke
Leah Faye Hefke
Notary Public.

My commission expires June 16, 1963



15095000330000

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Drilling Company
 CONTRACTOR: Musgrove Drilling Company
 FARM: TURNER #1
 LOCATION: SW SW SE Sec. 10-28S-5W
 Kingman County, Kansas
 COMMENCED: October 30, 1961
 COMPLETED: November 12, 1961

0	75	Red bed & sand
75	280	Red bed
280	850	Shale
850	1065	Shale & lime streaks
1065	1665	Lime & shale
1665	1905	Lime, shale & shells
1905	2235	Shale
2235	2975	Lime & shale
2975	3539	Lime
3539	3629	Lime & shale
3629	3768	Lime
3768	3805	Lime & chert
3805	3825	Mississippian
3825	3879	Lime & shale
3879	3887	Mississippian
	3887	Rotary Total Depgh

Set 8-5/8" surface at 241' w/200 sx Quick Set

DRY & ABANDONED

SCHLUMBERGER TOPS:	ELEVATIONS:	
Heebner 2694' (-1286)		1403' Gr.
Toronto 2757' (-1349)		1405' D. F.
Douglas Sh. 2780' (-1372)		1408' K. B.
Br. Lime 2952' (-1544)		
Lansing 2990' (-1582)		
Kans. City 3202' (-1794)		
Base K.C. 3429' (-2021)		
Mississippi 3788' (-2380)		

RECEIVED
 STATE CONSERVATION COMMISSION
 NOV 23 1961
 CONSERVATION DIVISION
 WICHITA, KANSAS

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the TURNER #1, SW SW SE Section 10-28S-5W, Kingman County, Kansas, as reflected by the files of Musgrove Drilling Company.

Emil E. Bowers
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 24th day of November, 1961.

Leah Faye Hefke
 Leah Faye Hefke, Notary Public

My commission expires June 16, 1963.