

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-047-20,193-0000 (of this well) 6/85
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. HOLL OPERATORS LICENSE NO. 5056

ADDRESS 6427 East Kellogg, Wichita, KS 67207 PHONE # (316) 684-8481

LEASE (FARM) ALDRICH WELL NO. 1 WELL LOCATION C SW SW COUNTY EDWARDS

SEC. 4 TWP. 24S RGE. 17 (E) or (W) (W) TOTAL DEPTH 4440' PLUG BACK TD 4400'

Check One:

OIL WELL X GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 247' KB CEMENTED WITH 225 SACKS

CASING SIZE 4 1/2" SET AT 4439' KB CEMENTED WITH 125 SACKS

PERFORATED AT 4356'-62'; 4330'-33'; 4059'-65'; 4050'-52'

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL heavy mud, hulls, cement

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? YES
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN as soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick / F. G. HOLL PHONE # (316) 995-3171

ADDRESS P. O. Box 158, Belpre, Kansas 67519 STATE CORPORATION COMMISSION 6-18-85

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347, Chase, KS 67524 CONSERVATION DIVISION Wichita, Kansas PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: W. J. Merrick
(Operator or Agent)

DATE: JUN 14 1985



IN CARLIN
HAEL LENNEN
GALEE WRIGHT
TH R. HENLEY
JITH A. MCCONNELL
AN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

SEP 18 1985

June 18, 1985

EXPIRES

WELL PLUGGING NOTICE

Aldrich #1
C SW SW
Sec. 4-24S-17W
Edwards County

F. G. Holl
6427 E. Kellogg
Wichita, KS 67207

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).

STERLING DRILLING COMPANY
 P. O. Box 129
 Sterling, Kansas 67579

WELL LOG - - - - - ALDRICH #1
 Located: C SW SW, Section 4-24E-17N, Edwards County, Kansas

OWNER: F. C. Goll
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 10, 1975

COMPLETED: November 18, 1975

TOTAL DEPTH: 4440'

LOG	
0 - 247	Sand and Shale
247 - 1059	Shale, Sand, Red Bed
1059 - 1078	Anhydrite
1078 - 2075	Shale and Shells
2075 - 3851	Lime and Shale
3851 - 4130	Lime
4130 - 4300	Lime and Shale
4300 - 4367	Lime, Sand, Chert
4367 - 4373	Chert and Lime
4373 - 4395	Lime and Shale
4395 - 4440	Lime and Chert

CASINGS RECORD

Ran 6 joints used 8 5/8" casing, 235' set at 247' K.B. Cemented with 225 sacks 60/40 Pozmix, 31 cc. Plug down at 9:45 PM, 11-10-75.

Ran 137 joints 4 1/2" casing, 4440' set at 4439 K.B. Cemented with 125 sacks Pozmix, 27 gal, 5" sugar and 3 bbl. water on plug. Plug down at 7:00 PM, 11-18-75.

RECEIVED
 STATE CORPORATION COMMISSION

JUN 18 1985

CONSERVATION DIVISION
 Wichita, Kansas