

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

RECEIVED  
STATE CORPORATION COMMISSION  
4-23-91  
APR 23 1991  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-047-21,295-0006 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. HOLL COMPANY OPERATORS LICENSE NO. 5056  
ADDRESS 6427 East Kellogg, Wichita, KS 67207 PHONE # (316) 684-8481  
P. O. Box 780167  
LEASE (FARM) JOHNSON WELL NO. 4 WELL LOCATION E/2 NE SW COUNTY Edwards  
SEC. 5 TWP. 24 RGE. 17W (E) or (W) TOTAL DEPTH 4521' LTD PLUG BACK TD 4494'

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_  
SURFACE CASING SIZE 8 5/8" SET AT 306' KB CEMENTED WITH 225 SACKS  
PRODUCTION CASING SIZE 4 1/2" SET AT 4517' KB CEMENTED WITH 225 SACKS  
PERFORATED AT 4348-4354 w/4 SPF

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL \_\_\_\_\_  
Heavy Mud, Hulls, Cement and Halliburton Plug

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick PHONE # (316) 995-3171

ADDRESS P. O. Box 158, Belpre, KS 67519

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347, Chase, KS 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Elwyn H. Nagel  
(Operator or Agent)  
Elwyn H. Nagel, Manager

DATE: April 23, 1991

①

Joan Finney  
Governor

Jim Robinson  
Chairman

Keith R. Henley  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian J. Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

May 1, 1991

F. G. Holl  
6427 East Kellogg  
Wichita, KS 67207

Johnson 4  
API 15-047-21,295-0060  
E/2 NE SW  
Sec. 05-24-17W  
Edwards County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760

15-047-21295-0000

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

HEBENEM  
CORPORATION  
APR 23 1991  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG ----- JOHNSON #4-5  
Located: E/2 NE SW, Section 5-24S-17W, Edwards County,  
Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 21, 1987

COMPLETED: October 28, 1987

TOTAL DEPTH: 4520'

## LOG

0 - 70 Surface Soil and Sand  
70 - 307 Clay, Shale  
307 - 650 Shale, Sand, Red Bed  
650 - 1167 Shale  
1167 - 1185 Anhydrite  
1185 - 4425 Lime and Shale  
4425 - 4520 Lime

## CASING RECORD

Ran 7 joints 8 5/8" casing. 291.25'  
pipe set at 304' K.B. Cemented with  
225 sacks 60/40 Pozmix, 2% gel and  
3% cc. Plug down at 6:30 PM,  
10-21-87, by Howco.

Ran 113 joints used 4 1/2" casing.  
4509.63' pipe set at 4517' K.B.  
Cemented with 100 sacks Lite and  
125 sacks F. G. Holl mix. Plug  
down at 5:00 AM, 10-28-87, by  
Howco.

Deviation Surveys: 3/4° at 2160'  
1° at 4350'