

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED FORM CP-1
Rev. 2/89
KANSAS CORPORATION COMMISSION

JAN 7 1991

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIVISION
WICHITA, KS

API NUMBER 15-047-20,403-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR F. G. Holl Company OPERATOR'S LICENSE NO. 5056 6-92
ADDRESS 6427 E. Kellogg P.O. Box 780167 PHONE # (316) 684-8481
Wichita, Kansas 67278-0167 440' FSL
LEASE (FARM) DECKERT WELL NO. 1 WELL LOCATION 1320' FEL COUNTY Edwards
SEC. 5 TWP. 24 RGE. 17W (E) or (W) TOTAL DEPTH 4463' LTD PLUG BACK TD 4415'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____
SURFACE CASING SIZE 8 5/8" SET AT 252' KB CEMENTED WITH 225 SACKS
CASING SIZE 4 1/2" SET AT 4460' KB CEMENTED WITH 150 SACKS
PERFORATED AT 4354-58 & 4391-94

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and Halliburton Plug.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick PHONE # (316) 995-3171

ADDRESS P.O. Box 158, Belpre, Ks. 67519

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050 6-92

ADDRESS Box 347, Chase, Ks. 67524 PHONE # (316) 938-2457

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Elwyn H. Nagel
(Operator or Agent)

DATE: January 6, 1992

①

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

January 7, 1992

F G Holl Company
6427 E Kellogg Box 780167
Wichita KS 67278-0167

Deckert 1
API 15-047-20,403-0000
440'FSL-1320'FEL
Sec. 05-24-17W
Edwards County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

Conservation Division
William R. Bryson
Director

200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

JAN 7 1991

CONSERVATION DIVISION
WICHITA, KSSTERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579WELL LOG ----- DECKERT #1-5
Located: 440' FSL, 1320' FEL, NE/4, Section 5-24S-17W,
Edwards County, KansasOWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling CompanyCOMMENCED: June 27, 1978
COMPLETED: July 5, 1978

TOTAL DEPTH: 4460'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 200 Sand, Clay	Ran 6 joints used 28#, 8 5/8" casing, 240.09' set at 252' K.B. with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 5:30 PM, 6-27-78.
200 - 255 Sand, Shale	
255 - 995 Shale, Sand and Red Bed	
995 - 1169 Red Bed	
1169 - 1191 Anhydrite	
1191 - 1775 Shale	
1775 - 2200 Shale and Lime Str.	
2200 - 4250 Lime and Shale	
4250 - 4355 Lime and Shale, Sand and Chert	
4355 - 4423 Cherty Lime	
4423 - 4460 Lime, Cherty Lime and Shale	Ran 103 joints new 10.5#, 4 1/2" casing, 445.79' set at 4460' K.B. with 50 sacks Howco Light, followed by 100 sacks Pozmix with 18% salt and 5# Gilsonite and 1/8# Flocele and 1/8# Tuffiber and 3/4% CFR-2 per sack. 250 gal. mud flush and 20 bbl. salt flush ahead of cement. Plug down at 8:15 AM, 7-5-78, by Howco.