

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,182-0000

LEASE NAME Deckert

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2-5

SPOT LOCATION SE SE NE

SEC. 5 TWP. 24 RGE. 17 (W)

COUNTY Edwards

LEASE OPERATOR F. G. Holl  
ADDRESS 6427 East Kellogg  
Wichita, Kansas 67207

Date Well Completed 7-4-84  
12:30 PM

PHONE # 816 ) 684-8481 OPERATORS LICENSE NO. 5056

Plugging Commenced 7-4-84  
1:45 PM,

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-4-84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing formation                      Depth to top                      bottom                      T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set.

Filled hole with heavy mud, plugged through open ended drill pipe -  
50 sacks at 1180'; 50 sacks at 310'; bridge, plug and 10 sacks at 40'. 15 sacks  
in rathole with joint of drill pipe, pulled water well and plugged with 5 sacks.  
Used 60/40 Pozmix plus 2% gel (4% total) and 3% cc.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142  
Address P. O. Box 129, Sterling, Kansas 67579

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF RICE, ss.

Harry J. Mead (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

III 06 1984  
7-6-84  
DIVISION  
WICHITA, KANSAS

(Signature) Harry J. Mead  
(Address) Harry J. Mead, Vice President  
P. O. Box 129, Sterling, Kansas  
67579

SUBSCRIBED AND SWORN TO before me this 5th day of July, 1984.

Agnes D. Wurst  
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85



**STERLING DRILLING CO.**

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - DECKERT #2-5

Located: SE SE NE, Section 5-24S-17W, Edwards County,  
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 28, 1984

COMPLETED: July 4, 1984

TOTAL DEPTH: 4500'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints new 8 5/8", 23# casing.
90 - 268 Clay, Shale	253.39' pipe set at 265' K.B.
268 - 978 Shale, Sand, Red Bed	Cemented with 210 sacks 60/40 Pozmix, 3% cc. Plug down at 4:15 PM, 6-28-84, by Halliburton.
978 - 1175 Shale	
1175 - 1195 Anhydrite	
1195 - 1488 Shale	
1488 - 2099 Shale and Lime Strg.	
2099 - 4404 Lime and Shale	
4404 - 4445 Chert and Shale	
4445 - 4500 Lime and Shale	Plugged.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 06 1984

WICHITA, KANSAS  
Wichita, Kansas

Deviation Surveys: 3/4° at 2161'  
1 1/2° at 4404'