

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,221-0000

LEASE NAME Wolfe Trust 2-13

WELL NUMBER _____

SPOT LOCATION SE NW NW

SEC.13 TWP. 24 RGE. 18 (W) or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 9/17/85

Plugging Completed 10/28/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg, Wichita, Ks. 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4611'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	293'	none
				4 1/2"	4597'	2138'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 40 sacks cement to 4318'. Shot pipe at 3517', 3231', 3014', 2814', 2621', 2409', 2216', & 2138'. Pulled 50 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8 5/8 plug, & 150 sacks 60/40 poz, 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address box 347, Chase, Ks. 67524

STATE OF Kanas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of October, 19 85

RECEIVED
Irene Hoover
STATE CORPORATION COMMISSION Notary Public

My Commission expires: _____



OCT 31 1985

Form CP-4
Revised 01-84

15-047-21221-0000

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- WOLFE TRUST #2-13
Located: SE NW NW, Section 13-24S-18W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 2, 1984

COMPLETED: November 9, 1984

TOTAL DEPTH: 4611'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 140 Sand and Clay	Ran 7 joints new 8 5/8" OD casing. 288.57' pipe set at 293' K.B.
140 - 303 Red Bed	Cemented with 235 sacks Common, 2% gel and 3% cc. Plug down at 3:00 PM, 11-2-84, by Howco.
303 - 1150 Lime and Shale	
1150 - 1895 Shale	
1895 - 2070 Shale and Lime Stringers	
2070 - 4611 Lime and Shale	Ran 113 joints 4 1/2", 10.5# casing. 4587.27' pipe set at 4597' K.B. 10 joints were used. Cemented with 250 sacks 50/50 Pozmix with regular additives. Plug down at 7:00 AM, 11-9-84, by Howco. Plugged water well and rathole.

Deviation Surveys: 1 1/2° at 2203'
2 1/4° at 4485'

AUG 20 1985