

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
APR 23 1991
4-23-81
6/91

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-047-20,181-0066 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. HOLL COMPANY OPERATORS LICENSE NO. 5056
ADDRESS 6427 East Kellogg, Wichita, KS 67207 PHONE # (316) 684-8481
P. O. Box 780167
LEASE (FARM) F. MASSEY WELL NO. 2 WELL LOCATION C E/2 NE COUNTY Edwards
SEC. 3 TWP. 24 RGE. 17W (E) or (W) TOTAL DEPTH 4395' RTD PLUG BACK TD NA

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8" SET AT 266' KB CEMENTED WITH 235 SACKS
PRODUCTION CASING SIZE 4 1/2" SET AT 4395' KB CEMENTED WITH 125 SACKS
PERFORATED AT 4294-4300

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____
Heavy Mud, Halls, Cement and Halliburton Plug

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick PHONE # (316) 995-3171

ADDRESS P. O. Box 158, Belpre, KS 67519

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347, Chase, KS 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Elwyn H. Nagel
(Operator or Agent)
Elwyn H. Nagel, Manager

DATE: April 23, 1991

①

Joan Finney
Governor

Jim Robinson
Chairman

Keith R. Henley
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian J. Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

May 1, 1991

F. G. Holl
6427 East Kellogg
Wichita, KS 67207

F. Massey 2
API 15-047-20, 181-0000
C E/2 NE
Sec. 03-24-17W
Edwards County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

15-047-20181-0000

RECEIVED
APR 23 1991
CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

15-047-20181-0000

WELL 100 - - - - - F. MASSEY #2
Located: C E/2 NE/4, Section 3-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 25, 1975
COMPLETED: September 2, 1975

TOTAL DEPTH: 4395'

<u>LOG</u>	
0 - 87	Sand and Clay
87 - 368	Shale
368 - 575	Sand and Shale
575 - 1450	Red Beds and Sand
1450 - 3845	Lime and Shale
3845 - 4220	Lime
4220 - 4320	Lime and Chert
4320 - 4365	Shale and Lime
4365 - 4385	Sand and Lime
4385 - 4395	Lime

CASING RECORD

Ran 77 joints 8 5/8" 28# casing, 255.31' pipe set at 266' K.B. Cemented with 235 sacks 60/40 Pozmix, 2% gel, 3% cc. Plug down at 6:15 PM, 8-25-75.

Ran 140 joints 4 1/2", 10.5#, 8RD, Rge #2 new casing. 4402.46' set at 4395' with 125 sacks Pozmix, salt saturated. Plug down at 9:30 AM, 9-2-75, by Howco.