

3 090676

3-8

324

API NUMBER 15- 073-23,514-00-00

SW SW NE, SEC. 3, T. 28 S, R. 10 X

feet from S section line

feet from E section line

Lease Name Stuber Well # 1

County Greenwood 82.23

Well Total Depth 2530 PBTB 2410 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 43

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Operator: Petroleum Management Inc.

Name & Address 400 N. Woodlawn

Wichita, Kansas 67208

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Long Drilling License Number

Address Box 131, Hamilton, Kansas 66853

Company to plug at: Hour: 10:00 am Day: 4 Month: 3 Year: 19 89

Plugging proposal received from Tom Long

(company name) (phone)

were: Set bridge above perfs. Set 50' cement plug. Rip and salvage pipe.

Pull pipe and set bridge at 700'. Spot 50' cement on bridge. Gel

to 350'. Cement 350' to surface.

RECEIVED
STATE CORPORATION COMMISSION

1989
4-11-89

Plugging Proposal Received by Benny E Beck (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:00 Day: 8 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT Set bridge and dumped 7 sacks cement with dump bailer.

Ripped pipe at 1710'. Pu-led pipe to 700', set bridge. Tied onto pipe

and pumped 5 sacks gel, then 15 sacks cement. Pulled pipe to 360'.

Pumped cement to surface with 90 sacks cement. Pulled pipe and topped

off hole with 10 sacks cement. Sun Cementing pumped the middle and

top plugs on Ticket #2471. I witnessed all three plugs.

Remarks:

(If additional description is necessary, use BACK of this form.)

I did / did not observe this plugging.

Signed Benny E Beck (TECHNICIAN)

DATE 4-21-89

INV. NO. 24434