

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20874-01-00  
Spot: NENWNWNW Sec/Twnshp/Rge: 36-29S-25W  
5256 feet from S Section Line, 4683 feet from E Section Line  
Lease Name: LUANN 2925 Well #: 2-36H  
County: FORD Total Vertical Depth: 5309 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	130		WITH 14 SX CMT
PROD	5.5	8422	0	WITH 940 SX CMT
SURF	9.625	1048		WITH 445 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2016 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5350' WITH 50 SX CMT. PLUG AT 1590' WITH 25 SX CMT. PLUG AT 1080' WITH 25 SX CMT. PLUG AT 500' WITH CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500 PSI

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2016 1:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5350' WITH 50 SX CMT. 1ST PLUG AT 1590' WITH 25 SX CMT. 2ND PLUG AT 1080' WITH 105 SX CMT TO SURFACE. PULLED TBG & TOPPED OFF WITH 5 SX CMT. 3RD PLUG PUMP 40 SX CMT ON BACKSIDE. PRESSURED TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
8185	8360		
7928	8148		
7669	7883		
7498	7799		
7366	7615		
6862	7058		
6614	6822		
6308	6564		
6027	6262		
5784	8185		
5519	5741		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES. TMD = 8422'.

Plugged through: TBG

District: 01

Signed [Signature] (TECHNICIAN) NO 5-6-16

RECEIVED  
APR - 5 2016  
KCC DODGE CITY

Received [Signature]  
KANSAS CORPORATION COMMISSION  
APR 11 2016  
CONSERVATION DIVISION  
WICHITA, KS