

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21979-01-00
Spot: SESWSESE Sec/Twnshp/Rge: 36-33S-5W
200 feet from S Section Line, 680 feet from E Section Line
Lease Name: GABRIEL 3305 Well #: 1-36H
County: HARPER Total Vertical Depth: 4590 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4915		
COND	20	100		8 SX
	11 7	5267		360 SX
PROD	4.5	9264		0 SX
SURF	9.625	550		340 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2016 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RON ORR Company: ORR ENTERPRISES, INC. Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/28/2016 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP AT 4800', CIRCULATED CASING WITH PLUG AND SPOTTED 40 SKS ON BP. RECOVERED 1422' OF 7" CASING AND PULLED FROM THE WELLBORE. RAN TUBING TO 1250' AND SPOTTED 50 SKS OF CEMENT. PULLED TUBING TO 600' AND SPOTTED 50 SKS OF CEMENT. PULLED TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE WITH 85 SKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
9052	9165		
8753	8958		
8416	8685		
7998	8348		
7624	7898		
7188	7494		
6822	7118		
6430	6743		
6158	6368		
5710	6060		
5334	5604		
4963	5100		

4699'
inv

Remarks: CLASS C CEMENT. ORR ENTERPRISES. MD = 9289

Plugged through: TBG

District: 02

Received
KANSAS CORPORATION COMMISSION

APR 26 2016

CONSERVATION DIVISION
WICHITA, KS

Signed _____

(TECHNICIAN)

no
5-6-16